

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

STATION:	SALEM		
SYSTEM:	Reactivity Control (SF1) - Control Rod Drive System (CRDS)		
TASK:	Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011		
TASK NUMBER:	0220040101		
JPM NUMBER:	17-01 NRC Sim-a		
ALTERNATE PATH:	<input checked="" type="checkbox"/>	K/A NUMBER:	001 A2.01
APPLICABILITY:		IMPORTANCE FACTOR:	<u>3.1</u> <u>3.7</u>
EO <input type="checkbox"/>	RO <input checked="" type="checkbox"/>	STA <input type="checkbox"/>	SRO <input checked="" type="checkbox"/>
EVALUATION SETTING/METHOD:	Simulator / Perform		
REFERENCES:	S2.OP-AR.ZZ-0011, Rev 60 (checked 6-22-18) S2.OP-SO.CBV-0001, Rev 34		
TOOLS AND EQUIPMENT:	None		
VALIDATED JPM COMPLETION TIME:	<u>5 min</u>		
TIME PERIOD IDENTIFIED FOR TIME CRITICAL STEPS:	<u>N/A</u>		
Developed By:	R. Chan <i>Rudolph Chan</i> Instructor	Date: 6-22-18	
Validated By:	<i>Michael Spencer</i> SME of Instructor	Date: <u>6/22/18</u>	
Approved By:	<i>Thomas Wathey</i> Training Department	Date: <u>10/30/18</u>	
Approved By:	<i>MERS</i> Operations Department	Date: <u>10/23/18</u>	
ACTUAL JPM COMPLETION TIME:			
ACTUAL TIME CRITICAL COMPLETION TIME:			
PERFORMED BY:			
GRADE:	<input type="checkbox"/> SAT	<input type="checkbox"/> UNSAT	
REASON, IF UNSATISFACTORY:			
EVALUATOR'S SIGNATURE:			DATE:

OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE

REVISION HISTORY

JPM NUMBER: 17-01 NRC Sim-a

Rev #	Date	Description	Validation Required
00	9-15-17	Added revision history and simulator setup pages. Editorial comments from IP 71111.11 FASA.	Yes
01	3-12-18	New for 2018 LOR Annual Exam. This task aligns with Safety Function #1 K/A.	Yes

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

SIMULATOR SETUP INSTRUCTIONS

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011

TASK NUMBER: 0220040101

SIMULATOR IC: IC-230 [6-22-18, 13:09:31]

MALFUNCTIONS:

1. Reset the simulator to the above IC #.
2. Ensure 21 and 22 CRD Vent Fans are running; 23 in standby.
3. Verify the following events on the Summary/ET Trigger Lists:

MALF ID #	Description	Delay Time	Initial Value	Ramp Time	Trigger	Severity
01	RD0316A, 21 CRD Vent Fan damper fails close	N/A	N/A	N/A	RT-1	TRUE
02	VC0316C, 23 CRD Fan Trip	00:00:40	N/A	N/A	ET-1	TRUE
03	VC0316B, 22 CRD Fan Trip	00:00:50	N/A	N/A	ET-1	TRUE

4. These malfunctions will simulate the running CRDM Vent Fan dampers closing resulting in air flow lo console alarm. IAW ARP, the standby fan will be started. **ALTERNATE PATH:** Seconds later the standby fan trips followed by the last remaining running fan (no CRDM Fans running). IAW ARP, the operator is required to TRIP the Reactor.

OVERRIDES / REMOTES:

ID #	Description	Delay Time	Initial Value	Ramp Time	Trigger	Condition/Severity

EVENT TRIGGERS:

ET#	Description	Command
1	KAB05PBR, 23 CRD Vent Fan Start PB	

SPECIAL INSTRUCTIONS: None

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

NAME: _____

DATE: _____

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011.

TASK NUMBER: 0220040101

INITIAL CONDITIONS:

- Unit 2 at 100% power, BOL.
- No equipment is out of service and no active Tech Specs are in effect.

INITIATING CUE:

- You are the Reactor Operator.
- Respond to all alarms and indications.

Successful Completion Criteria:

1. All critical steps completed.
2. All sequential steps completed in order.
3. All time-critical steps completed within allotted time.
4. JPM completed within validated time. Completion time may exceed the validated time if satisfactory progress is being made (and NRC concurrence is obtained).

Task Standard for Successful Completion:

1. STARTs Standby CRDM Vent Fan IAW ARP based on abnormal console indications.
2. TRIPs the Reactor IAW ARP based on no CRDM Vent Fans running.

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011

* #	STEP NO.	STEP (Shaded area denotes Critical Step) (* Critical Step)	STANDARD (Bolded area identifies Task Standard)	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
	CUE	Fill in the JPM Start Time when the student acknowledges the Initiating Cue. START TIME: _____			
	CUE	Simulator Operator: INSERT RT-1 when the operator assumes the watch. MALF: RD0361A 21 CRD Vent Fan Damper Failure			
		The following alarm and indication will come in following RT-1 for <u>21 CRDM Vent Fan</u> : <ul style="list-style-type: none"> ▪ AIR FLOW LO ▪ SEQUENCE COMPLETE bezel extinguished (NOT Illuminated) 	Operator reports receipt of unexpected console alarm on 21 CRD Vent Fan for AIR FLOW LO and the SEQUENCE COMPLETE bezel extinguished. Operator refers to 2CC1 ARP. CUE: IF operator reports to you as CRS the following alarms AND is waiting for direction; THEN state: CRS directs you to respond to alarms and indications IAW applicable Alarm Response Procedures.		
	CUE	The following steps are from Alarm Response Procedure (ARP) S2.OP-AR.ZZ-0011 , CONTROL CONSOLE 2CC1	Evaluator's Note: The operator may also refer to S2.OP-SO.CBV-0001, Containment Ventilation Operation, section 5.4 for starting/stopping CRDM Vent Fans. <u>However, this procedure provides NO direction for a loss of all CRDM Vent Fans.</u>		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011

* #	STEP NO.	STEP (Shaded area denotes Critical Step) (* Critical Step)	STANDARD (Bolded area identifies Task Standard)	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
	2CC1 ARP pg 13	CONTAINMENT VENTILATION SYSTEM Rod Drive Vent Fans AIR FLOW LO	Operator responds to console alarm for AIR FLOW LO and refers to 2CC1 ARP S2.OP-AR.ZZ-0011 page 13.		
	1.0	CAUSE(S): Fan discharge pressure < 2.0 INWC.	Operator reads the step and continues on.		
	2.0	AUTOMATIC ACTIONS: None	Operator reads the step and continues on.		
	3.0	OPERATOR ACTIONS:			
	NOTE	Low flow alarm may result from erratic flow during fan start. Illumination of control console SEQUENCE COMPLETE light indicates flow through fan outlet damper. Alarm should clear when fan is up to speed.	Operator reads the Note and continues on.		
	CAUTION	Operating with less than two Rod Drive Vent Fans in service could degrade the Rod Drive Coils. An Operability Determination should be performed when operating with one Rod Drive Vent Fan. Operating with more than two Rod Drive Vent Fans in service could damage the fan blades.	Operator reads the Caution and determines this is not applicable at this time, unless the standby fan does not start. Operator continues on. CUE: IF operator informs CRS of Caution, THEN state: the CRS will review this Caution for potential Operability Determination requirements.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011

* #	STEP NO.	STEP (Shaded area denotes Critical Step) (* Critical Step)	STANDARD (Bolded area identifies Task Standard)	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
	3.1	<p>IF Rod Drive Vent Fan has just been started, AND SEQUENCE COMPLETE indication is illuminated, THEN MONITOR both running Rod Drive Hdr Outlet temperatures.</p> <p>Fan Comp Pt / Alrm Description 21 T2602A / 160°F 21 Rod Drive Hdr Outlet Temp 22 T2603A / 160°F 22 Rod Drive Hdr Outlet Temp 23 T2604A / 160°F 23 Rod Drive Hdr Outlet Temp</p>	<p>Operator reads the step and determines that a Vent Fan has NOT been started.</p> <p>Marks step N/A and continues on.</p>		
*	3.2	<p>IF SEQUENCE COMPLETE indication for affected fan is extinguished THEN immediately SWAP to the standby Rod Drive Vent Fan,</p> <p>(Evaluator's Note: Steps A-E are below)</p>	<p>Operator determines these steps are applicable based on the SEQUENCE COMPLETE indication bezel is extinguished.</p> <p>Operator continues on and PERFORMS the applicable steps.</p> <p>Evaluator's Note: It is acceptable for the operator to Stop and Start CRD Vent Fans using S2.OP-SO.CBV-0001.</p>		
*	3.2.A	PRESS STOP for affected Rod Drive Vent Fan	Operator depresses STOP PB for 21 Fan and verifies STOP bezel illuminates Green.		
*	3.2.B	PRESS START for standby Rod Drive Vent Fan	Operator depresses START PB for standby vent fan and verifies START bezel illuminates RED. Operator reports SEQUENCE COMPLETE bezel is illuminated and AIR FLOW LO is extinguished as expected.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011

* #	STEP NO.	STEP (Shaded area denotes Critical Step) (* Critical Step)	STANDARD (Bolded area identifies Task Standard)	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
	CUE	<p>Simulator Operator: ENSURE ET-1 is TRUE when the standby fan is started. This will INSERT VC0316C and VC0316B to Trip the two (2) running Vent Fans after a time delay.</p> <p>MALF VC0316C 23 CRD Fan Trip Delay = 00:40 seconds MALF VC0316B 22 CRD Fan Trip Delay = 00:50 seconds.</p>			
	3.2.C	IF the standby fan can NOT be started, AND at least one Rod Drive Vent Fan is in operation, THEN PERFORM an Operability Determination to determine continued plant operation [80083830].	Operator marks step as N/A based on standby fan starting.		
ALTERNATE PATH STARTS HERE:		Loss of ALL CRDM Vent Fans			
*	3.2.D	<p>IF there are NO Rod Drive Vent Fans in operation, THEN:</p> <p>1. TRIP the Reactor</p> <p>2. GO TO 2-EOP-TRIP-1, Reactor Trip or Safety Injection</p>	<p>Operator initially marks this step as N/A based on standby fan starting.</p> <p>This step will become applicable when the two (2) running vent fans trip shortly after.</p> <p>Operator TRIPs the Reactor when NO Vent Fans are in operation.</p> <p>Terminate the JPM when Rx is Tripped</p> <p>Evaluator's Note: Performing EOP-TRIP-1 immediate actions is <u>not</u> required to complete this JPM.</p>		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011

* #	STEP NO.	STEP (Shaded area denotes Critical Step) (* Critical Step)	STANDARD (Bolded area identifies Task Standard)	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
	3.2.E	IF at least one Rod Drive Vent Fan is in operation, THEN INITIATE a NOTF to determine and correct the cause of the low flow.	Operator determines this step is N/A and continues on.		
	3.3	SEND an operator to check the main and backup breakers closed for the affected fan.	CUE: CRS will dispatch an operator to check the breaker positions for the main and backup breakers for 21 CRD Vent Fan.		
	NOTE	Main breakers are on 84', 460/230V Switchgear Room	Operator reads the Note and continues on.		
	3.3.A	IF a breaker is found tripped, THEN INFORM the Unit 2 Control Room. 21 Fan Main Bkr 2EX1AX5X Backup Bkr 2EX1AX5X-1	Operator awaits report from field operator and continues on.		
	3.3.B	INITIATE a NOTF to determine and correct cause of the breaker trip.	Operator awaits report from field operator and continues on.		
	3.4	MONITOR running Rod Drive Hdr Outlet temperature(s). Fan Comp Pt / Alrm Description 21 T2602A / 160°F 21 Rod Drive Hdr Outlet Temp 22 T2603A / 160°F 22 Rod Drive Hdr Outlet Temp 23 T2604A / 160°F 23 Rod Drive Hdr Outlet Temp	Operator monitors running Vent Fan Outlet temperatures on the P250 computer.		
	3.5	INITIATE a NOTF to determine and correct cause of the of the low flow alarm	Operator informs CRS to initiate NOTF. CUE: CRS will initiate the notification.		

**OPERATOR TRAINING PROGRAM
JOB PERFORMANCE MEASURE**

SYSTEM: Reactivity Control (SF1) - Control Rod Drive System (CRDS)

TASK: Respond to Loss of All Control Rod Drive Vent Fans IAW S2.OP-AR.ZZ-0011

* #	STEP NO.	STEP (Shaded area denotes Critical Step) (* Critical Step)	STANDARD (Bolded area identifies Task Standard)	EVAL S/U	COMMENTS (Required for UNSAT evaluation)
	CUE:	<p>JPM is complete when the task is complete OR at the direction from the Lead Evaluator.</p> <p>RECORD the STOP TIME.</p> <p>STOP TIME: _____</p>	<p>Terminate the JPM when the operator TRIPs the Reactor.</p> <p>Evaluator's Note: Operator performing immediate actions of EOP-TRIP-1 is <u>not</u> required for this task.</p>		

OPERATIONS DEPARTMENT
JOB PERFORMANCE MEASURE

TQ-AA-106-0303

JPM: 17-01 NRC Sim-a

JOB PERFORMANCE MEASURE VALIDATION CHECKLIST

NOTE: All steps of this checklist should be performed upon initial validation. Prior to JPM usage, revalidate JPM using steps 8 and 11 below.

- JK 1. Task description and number, JPM description and number are identified.
- JK 2. Knowledge and Abilities (K/A) references are included.
- JK 3. Performance location specified. (in-plant, control room, or simulator)
- JK 4. Initial setup conditions are identified.
- JK 5. Initiating and terminating Cues are properly identified.
- JK 6. Task standards identified and verified by SME review.
- JK 7. Critical steps meet the criteria for critical steps and are identified with an asterisk (*).
- JK 8. Verify the procedure referenced by this JPM matches the most current revision of that procedure: Procedure Rev. 60 Date 6/22/18 S2.OP-AR.22-0011
34 6/22/18 S2.OP-SD.CBU-0001
- JK 9. Pilot test the JPM:
 - a. verify Cues both verbal and visual are free of conflict, and
 - b. ensure performance time is accurate.
- NA^R 10. If the JPM cannot be performed as written with proper responses, then revise the JPM.
- NA^R 11. When JPM is revalidated, SME or Instructor sign and date JPM cover page.

SME/Instructor: Michael Spencer / Michael Spencer Date: 6/22/18
SME/Instructor: Thomas Wathey / Thomas Wathey Date: 6/22/18
SME/Instructor: _____ Date: _____

**OPERATIONS DEPARTMENT
JOB PERFORMANCE MEASURE**

INITIAL CONDITIONS:

- Unit 2 at 100% power, BOL.
- No equipment is out of service and no active Tech Specs are in effect.

INITIATING CUE:

- You are the Reactor Operator.
- Respond to all alarms and indications.